

Formigine

Ns. rif. : Sig. Cuoghi Andrea

ROAD TOWED TRAILER MODEL TBTO 20 READY FOR DELIVERY



In response to your kind request, with the present we are to offer our ns. best offer for the supply of a Towed Trailer for the handling of 20 Ton model TBTO20 boats.

<input type="checkbox"/> Capacity	Ton.	20
<input type="checkbox"/> Length	mm.	11.525
<input type="checkbox"/> Width	mm.	2.980
<input type="checkbox"/> Height min	mm.	942
<input type="checkbox"/> Height max	mm.	952
<input type="checkbox"/> Lifting	mm.	200



LIFTING AND MOVEMENTS OF THE BOAT

On board the trailer a hydraulic power unit is installed, powered by a 200 toH battery, which controls the hydraulic lifting (front and rear independent) of the trolley.

Alongside the base structure, there are 8 housings where the mobile telescopic candles can be applied, which allow the boat to be supported by rubber-covered support plates applied with appropriate joints in the terminal part of the same, allowing the blocking the boat on the trolley, or the revolving forks that allow the lifting of sailboats through reservoirs.

The lifting stroke of the candles in question is 500 mm. The lifting stroke of the complete trolley is 200 mm. The trolley adapts easily to any shape of the ground on which it operates and to the shape of the boat thanks to its ability to hydraulically incline the front and rear part of the trolley by the operator and the vertical stroke of the telescopic candles.

ANTI-CORROSION PROTECTION:

Once the trailer structural work has been completed, this shall undergo the following treatment:

- SA 2.5 degree sandblasting of all the structural works upon work completion.
- Application of an epoxy anti-rust primer with 120 micron thickness,
- Application of two coats of epoxy enamel paint Blu Mare [Sea Blue] (RAL. 5017) with 80 micron thickness,

This complete treatment will ensure a minimum dry film thickness of 180 micron.

ASSISTANCE DURING ASSEMBLY:

Abi-Trailers will send one engineer to give assistance during assembly, you will have to put at his disposal at least two persons (if it is possible, the same persons who will operate the boat trailer). They will be instructed by our supervisor for the complete assembly and test then, they will also be duly trained for operation and maintenance.

SUPPLY CONDITION

- DELIVERY TIME** : 15 days (Summer/Xmas holidays excluded) - The delivery period starts with the day on which agreement was made in every technical and commercial detail for the supply and does not begin before the receiving of the down payment.
The period of delivery is automatically prolonged should one of the following circumstances occurs: - If the payments are not promptly made
- If the Customer does not supply the necessary data for the preparation of the equipment within reasonable time and does not promptly approve the designs and the layouts of implementation, where this should be requested.
 - If the Client requests substantial changes during the carrying out of the order.
 - If the Client does not supply any possible material that he should, within a reasonable time
 - Should there be causes that, independent of ABI TRAILERS good will and intention, delay the delivery
 - Should there be reasons beyond our control
- DELIVERY TERMS ... :** ex-works ABI TRAILERS factory
- PAYMENT** : 40% in advance with the order
60% before shipping

WARRANTY : 12 months who's the first 6 months are fully covered (local expenses are excluded). The second 6 months are restricted to the replacement or repairing of the faulty parts (machine components or parts of the machine) – are excluded the Intervention/assembly/disassembly costs and transport cost.



Andrea Cuoghi / Sales Manager
M: +39 320 4096472
T: +39 059 7409130
E-mail/Skype: acuoghi@ascom-italy.it
Ascom S.p.A.
<http://www.ascom-italy.it>